

T Level Technical Qualification in **Building Services Engineering for Construction**

EMPLOYER-SET PROJECT

Project Brief

610/5780/0



Version History

Version	Author	Date	Change Description
1.0	JW	12/05/25	First introduction

Contents

Project Brief 3

SAMPLE

Project Brief

The employer

New Horizons Construction is an established building contractor with branches throughout the UK. Each branch works on different types of developments including new build residential and commercial retail.

The project

New Horizons Construction is preparing a tender submission for an extension to an existing primary school to provide extra space. The tender specification includes the requirement to include new building methods and renewable technologies to showcase environmental and sustainable awareness in the construction industry.

You are part of the team who is working together to respond to the tender. You must research technologies including modular build methods, renewable energy and water saving products. You must contribute to planning in line with the end client requirements.

An extract of the tender specification, including the relevant sections relating to your part of the project, has been provided. This includes site plans, supplier details and budget details.

SAMPLE

Tender Specification

Primary school extension project

Supplier list

Purchasing technologies directly from manufacturers is preferred. This is to ensure value for money and inclusion in manufacturer servicing programmes. Potential suppliers include:

- www.gcscabins.co.uk/modular-builds
- www.jcpsa.co.uk/news/what-is-modular-construction/
- www.renewableenergyhub.co.uk/
- www.theheatpumpwarehouse.co.uk
- www.edfenergy.com/heating/heat-pumps/air-source-heat-pump-guide
- www.thetankshop.co.uk
- <https://www.treehugger.com/beginners-guide-to-rainwater-harvesting-5089884>
- www.rainharvesting.co.uk

Building specification/technology requirements

Orientation:	South facing
PV system requirements	8kW System
Air source heat pump requirements	12kW system
Rainwater harvesting tank requirements	40,000 litres

The extension will be constructed via a modular build system. This will be constructed off-site and installed on-site during the school summer holidays.

To ensure the efficient use of energy, the extension should have a building management system (BMS) that controls heating and lighting (for peak and off-peak times) throughout the building.

The extension should include low energy lighting options within the building.

The extension should, as far as possible, incorporate renewable technologies as part of the finished development, including:

- water conservation
- electricity producing technologies
- electrical energy conservation.

For land optimisation, underground rainwater tank(s) should be installed.

To prevent the wastage of water and to ensure water efficiency throughout the building, the extension should incorporate the following water conservation technologies:

- spray taps
- low volume flush WC
- flow reducing valves
- infrared taps/WC flushing.

Systems budget

Projected system costs based on technology requirements:

Modular build budget:

- £125,000 - £150,000 for a 12-meter x 12.8-meter modular build
- £23,000 - £25,000 for delivery (includes crane hire, installations, police escort for sizes over 3.1 meters)
- £50,000 - £55,000 for groundworks (includes modular build base, water, waste, plumbing, electrical, data services).

Water conservation budget:

- Rainwater harvesting £20,000 - £25,000 (includes £2,000 labour costs).

Electricity producing technology budget:

- Solar PV £12,000 - £13,500 (includes £3,000 labour costs).

Heat producing technology budget


- Air Source Heat pump £7,500 - £8,500 (that includes £2,000 labour costs).

Duration


Installation of the modular building and renewable technologies, for the school extension, should take no more than 30 days. This needs to be completed within the 6-week summer holiday period.

Systems will be commissioned by the manufacturers, therefore commissioning does not need to be taken into consideration within this 30 day duration.


MEWNOL - INTERNAL




MEWNOL - INTERNAL




West Elevation



North Elevation





East Elevation



South Elevation


Client: Yurton Academy	Location: Manchester
Drawn By: PAE	Drawn Date: 12/03/16
Sheet Size: A3	Drawing Scale: 1:100
Drawing Title: Two Classroom Extension General Arrangement Elevations	

MEWNOL - INTERNAL



Client: Yurton Academy	Location: Manchester
Drawn By: PAE	Drawn Date: 12/03/16
Sheet Size: A3	Drawing Scale: 1:75
Drawing Title: Two Classroom Extension General Arrangement Sections	

MEWNOL - INTERNAL



Client:	Yurton Academy	Location:	Manchester
Drawn By:	PAE	Drawn Date:	12/03/16
Sheet Size:	A3	Drawing Scale:	1:150
Drawing Title: Two Classroom Extension Isometric Views			

Contact Us

WJEC Eduqas
245 Western Avenue
Cardiff
CF5 2YX
Tel: 029 2026 5465
Email: tlevels@eduqas.co.uk
Website: www.eduqas.co.uk

Copyright in this document belongs to, and is used under licence from, the Institute for Apprenticeships and Technical Education, © 2025.

‘T-LEVELS’ is a registered trade mark of the Department for Education.

‘T Level’ is a registered trade mark of the Institute for Apprenticeships and Technical Education.

‘Institute for Apprenticeships & Technical Education’ and logo are registered trade marks of the Institute for Apprenticeships and Technical Education.

The T Level Technical Qualification is a qualification approved and managed by the Institute for Apprenticeships and Technical Education.

WJEC is authorised by the Institute for Apprenticeships and Technical Education to develop and deliver this Technical Qualification.

WJEC operates in England under the name Eduqas which is a registered trademark of WJEC.